#### ETSI WP TM4 work on P-MP/P-P Co-existence

Cover Sheet for Presentation to IEEE 802.16 Broadband Wireless Access Working Group (Rev. 1)

Document Number:

**IEEE** 802.16lp-00/07r1

Date Submitted:

2000-03-06

Source:

Barry Lewis, ETSI TM4 Liaison Officer Voice: +44 207 211 0313 Radiocommunications Agency Fax: +44 207 211 0115

Wyndham House E-mail: lewisb@ra.gtnet.gov.uk

189 Marsh Wall, London E14 9SX

Venue:

802.16.2, **802.16 Session #6**, Albuquerque, 6th- 9th March 2000

Base Document:

IEEE 802.161-00/07r1

Purpose:

The presentation supports a liaison document supplied by ETSI WP TM4. It is considered as being of interest to the work of the 802.16.2 co-existence group. It is the latest draft under work item DETR/TM-04069.

Notice:

This document has been prepared to assist the IEEE 802.16. It is offered as a basis for discussion and is not binding on the contributing individual(s) or organization(s). The material in this document is subject to change in form and content after further study. The contributor(s) reserve(s) the right to add, amend or withdraw material contained herein.

Release:

The contributor acknowledges and accepts that this contribution may be made public by 802.16.

IEEE Patent Policy:

The contributor is familiar with the IEEE Patent Policy, which is set forth in the IEEE-SA Standards Board Bylaws <a href="http://ieee802.org/16/ipr/patents/bylaws.html">http://ieee802.org/16/ipr/patents/bylaws.html</a> and includes the statement:

"IEEE standards may include the known use of patent(s), including patent applications, if there is technical justification in the opinion of the standards-developing committee and provided the IEEE receives assurance from the patent holder that it will license applicants under reasonable terms and conditions for the purpose of implementing the standard."

See <a href="http://ieee802.org/16/ipr">http://ieee802.org/16/ipr</a> for details.

#### TM4 Work Items

- Items potentially of interest (i.e.BFWA oriented):
  - MWS at 40GHz early draft
  - Antennas for MWS at 40GHz
  - WI 04069 Co-existence Issues \*\*
  - WI 04087 TDD/FDD Issues
  - Stds at 26/28GHz (EN 301-213 Pts 1-4)

# ETSI WP-TM4 Work Item DETR/TM-04069

Rules for coexistence of P-P and P-MP systems using different access methods in the same frequency band.

IEEE 802.161-00/07r1

#### Scope


- Systems intended to operate:
  - in the same frequency band.
  - in the same or near geographical area.
- Methodologies for evaluating interference
- Identifies critical parameters
- Mitigation methods

## Deployment Scenario

#### P-MP assumptions

- Number of operators in any given area in any frequency band.
- Operator plans his own network.
- Systems may supply differing services.
- Different access methods might be used.
- Frequency block assignments.
- Some deployment constraints could result.

## Typical Freq Plan



#### Interference Classes

#### With FDD freq. Plan in mind:

- Class A1: (down/down adjacency)
  - CS interferer into victim TS
- Class A2: (up/up adjacency)
  - TS interferer into victim CS
- Class A3: (down/up adjacency)
  - CS interferer into victim CS
- Class A4: (up/down adjacency)
  - TS interferer into TS victim

#### Interference Scenarios

- P-MP FDD/FDD
  - Classes A1 to A4
- P-MP FDD/TDD
  - Specific cases of classes A1 to A4
- P-MP TDD/TDD
  - Specific cases of classes A1 to A4
- P-MP to P-P
  - Classes B1 to B4

## Methodology

- Net Filter Discrimination
  - Emitted Spectrum & Rx system filtering
  - Ratio of power transmitted to that "visible" after rx filter.
- Generic Scenario for each class.
- Evaluation parameters
  - separation distances
  - -C/I

## Considerations (1)

- Class A1 (Int. from CS to victim TS)
  - Site sharing improves co-existence
  - Possibly without guard bands
  - Near siting helps also.
  - With no site sharing, at least one channel guard required.(Overlapping cell problem).
  - Small interfered area exists
  - Co-existence etiquette required.

## Considerations (2)

- Class A2 (Int. from TS to victim CS)
  - Same as Class A1.
- Class A3 (Int. from CS to adjacent victim CS)
  - Site sharing not possible / minimum separation required.
  - Guard band required to minimise separation distance.

## Considerations (3)

- Class A4 (Int. from TS to adjacent victim TS)
  - guard band required
  - exacerbated by large numbers of TS

#### Useful Rules

- Best possible NFD reduces guard bands.
  - Rx "masks" not defined in standards though.
- Similar EIRP's at CS reduces Class A1 interference.
- Use of RTPC reduces guard band requirements.
- Equal channelisation and similar receiver performance reduces guard bands.

## Frequency planning

- Defined uplink and downlink sub-bands for FDD systems limits scenarios to Classes A1 and A2.
- Introduction of TDD requires Class A3 to be considered requiring guard bands.

## Examples

- 3.5GHz band
  - Generally suggests 3.5MHz (1 channel) guard satisfactory if "actual" characteristics used.
- TDMA systems in 26GHz Band
  - Generally suggests that site (or near) sharing possible with no guard band for identical systems.
  - Better NFD's could cover non identical systems
  - − 1 channel guard for non co-ordinated use.

## Another Example

- FDMA and TDMA system in 26GHz Band
  - Differing parameter characteristics require one (largest) channel guard band even if site sharing possible.
  - 2 channel guard required for non co-ordinated deployment.

#### Status of Work

- Approval anticipated at next TM4 plenary (June 2000).
- All previous examples were FDD
- Further FDD/TDD issues being tackled in work item DETR/TM-04087 (TDD in P-MP FWA systems).

#### Proposal

- Willing to provide input for Section 5 in Recommended Practice (TM4 approved)
  - Work of other standardisation bodies
  - Outline scope of this work
  - Detail interference scenarios addressed
  - Outline methodologies proposed
  - Highlight the main conclusions/recommendations.
- Feedback to TM4 from 802.16