Project	IEEE 802.16 Broadband Wireless Access Working Group <http: 16="" ieee802.org=""></http:>				
Title	Mobile Relay Station Preamble Segment Re-Assignment Scheme				
Date Submitted Source(s)	2006-01-18				
	Peter Wang, Adrian Boariu, Shashikant Maheshwari, Yousuf Saifullah Nokia 6000 Connection Drive, Irving, TX	Voice: +1 214-912-4613 Fax: peter.wang@nokia.com			
	Eugene Visotsky Philippe Sartori Motorola Labs 1301 E. Algonquin Rd. Schaumburg, IL 60196	Voice: +1-847-538-9458 eugenev@motorola.com			
	Shyamal Ramachandran Motorola Inc. 1064 Greenwood Blvd. Suite 400 Lake Mary, FL 32746	Voice: +1 - 407-562-4054 Shyamal.Ramachandran@motorola.com			
	I-Kang Fu, Wern-Ho Sheen, Fang-Ching Ren NCTU/ITRI ED922, 1001 Ta Hsueh Road, Hsinchu, Taiwan, R.O.C	IKFu@itri.org.tw			
	Sungkyung Kim, Sungcheol Chang, Chulsik Yoon ETRI 161, Gajeong-dong, Yuseong-Gu, Daejeon, 305-350, Korea	cyrano@etri.re.kr			
	Kanchei (Ken) Loa, Yi-Hsueh Tsai, Shiann- Tsong Sheu, Hua-Chiang Yin, Chih-Chiang Hsieh, Yung-Ting Lee, Frank C.D. Tsai, Heng-Iang Hsu, Youn-Tai Lee Institute for Information Industry 8F., No. 218, Sec. 2, Dunhua S. Rd., Taipei City, Taiwan.	Voice: +886-2-2739-9616 loa@iii.org.tw			
	Aik Chindapol Siemens Corporate Research 755 College Road East, Princeton, NJ, USA	Voice: +1 609 734 3364 Fax: +1 609 734 6565 Email: <u>aik.chindapol@siemens.com</u>			
	Yong Sun, Dharma Basgeet, Fang Zhong, Khurram Rizvi, Paul Strauch Toshiba Research Europe Limited 32 Queen Square, Bristol BS1 4ND, UK	Tel. no. +441179060749 Sun@toshiba-trel.com			
	Matty Levanda WiNetworks 32 Maskit St. Hertzlia, Israel	mattyl@winetworks.com			

	Voice 617-621-(7557,7527)			
	Fax 617 621 7550 {teo, tao, jzhang}@merl.com			
Cambridge, MA 02421 USA				
David Comstock, John Lee,	dcomstock@huawei.com			
Zheng Shang, Jingning Zhu	Voice: +1 858 735 9382			
•				
P.R.C				
Yanling Lu, Ting Li	luyanling@hisilicon.com			
	Voice: 86-10-82829010 Fax: 86-10-82829075			
Road, HaiDian District, Beijing, China	rax: 80-10-82829073			
Sean Cai, Qu Hongyun	scai@zteusa.com			
ZTE USA	Voice: 86-755-26776604			
Daqing Gu, Anxin Li				
	Gu@docomolabs-beijing.com.cn Voice: +86-10-8286-1501 ex.309			
No.2 Kexueyuan South Rd, Haidian District, Beijing, 100080 China				
Call for Technical Proposals regarding IEEE Project P802.16j (IEEE 802.16j-06/027)				
This contribution proposes mobile relay-station preamble and segment re-assignment scheme that mitigates system interference during mobility MRS handover.				
Propose the text regarding mobile relay-station preamble segment re-assignment for multi-hop relay systems				
Notice This document has been prepared to assist IEEE 802.16. It is offered as a basis				
and is not binding on the contributing individual(s) or organization(s). The material in this document is subject to change in form and content after further study. The contributor(s)				
The contributor grants a free, irrevocable license to the IEEE to incorporate material contained in this contribution, and any modifications thereof, in the creation of an IEEE Standards publication; to copyright in the IEEE's name any IEEE Standards publication even though it may include portions of this contribution; and at the IEEE's sole discretion to permit others to reproduce in whole or in part the resulting IEEE Standards publication. The contributor also acknowledges and accepts that this contribution may be made public by IEEE 802.16.				
The contributor is familiar with the IEEE 802.16 Patent Policy and Procedures < <u>http://ieee802.org/16/ipr/patents/policy.html</u> >, including the statement "IEEE standards may include the known use of patent(s), including patent applications, provided the IEEE receives assurance from the patent holder or applicant with respect to patents essential for compliance with both mandatory and optional portions of the standard." Early disclosure to the Working Group of patent information that might be relevant to the standard is essential to reduce the possibility for delays in the development process and increase the likelihood that the draft publication will be approved for publication. Please notify the Chair < <u>mailto:chair@wirelessman.org</u> > as early as possible, in written or electronic form, if patented technology (or technology under patent application) might be incorporated into a draft standard				
	David Comstock, John Lee, Zheng Shang, Jingning Zhu Huawei Technologies No.98, Lane91, Eshan Road, Shanghai, P.R.C Yanling Lu, Ting Li Hisilicon Technologies Harbour Building, No.8, Dongbeiwang West Road, HaiDian District, Beijing, China Sean Cai, Qu Hongyun ZTE USA Daqing Gu, Anxin Li DoCoMo 7/F, Raycom Infotech Park A, No.2 Kexueyuan South Rd, Haidian District, Beijing, 100080 China Call for Technical Proposals regarding This contribution proposes mobile relat that mitigates system interference durin Propose the text regarding mobile relay relay systems This document has been prepared to as and is not binding on the contributing i document is subject to change in form reserve(s) the right to add, amend or w The contributor grants a free, irrevocat in this contribution, and any modificati publication; to copyright in the IEEE's may include portions of this contribution reproduce in whole or in part the result acknowledges and accepts that this cor The contributor is familiar with the IEI <http: 16="" ieee802.org="" ipr="" patents="" polic<br="">include the known use of patent(s), inc assurance from the patent holder or app with both mandatory and optional port Group of patent information that might possibility for delays in the developme publication will be approved for public <mailto:chair@wirelessman.org> as ea</mailto:chair@wirelessman.org></http:>			

2

being developed within the IEEE 802.16 Working Group. The Chair will disclose this notification via the IEEE 802.16 web site http://ieee802.org/16/ipr/patents/notices.

Mobile Relay-Station Preamble Segment Re-Assignment Scheme

Peter Wang, Adrian Boariu, Shashikant Maheshwari, Yousuf Saifullah Nokia

Eugene Visotsky, Philippe Sartori, and Shyamal Ramachandran Motorola Labs

> I-Kang Fu, Wern-Ho Sheen, Fang-Ching Ren NCTU/ITRI

Sungkyung Kim, Sungcheol Chang, Chulsik Yoon ETRI

Kanchei (Ken) Loa, Yi-Hsueh Tsai, Shiann-Tsong Sheu, Hua-Chiang Yin, Chih-Chiang Hsieh, Yung-Ting Lee, Frank C.D. Tsai, Heng-lang Hsu, Youn-Tai Lee Institute for Information Industry

> Aik Chindapol Siemens Corporate Research

Yong Sun, Dharma Basgeet, Fang Zhong, Paul Strauch Toshiba Research Europe Limited

> Matty Levanda WiNetworks

Koon Hoo Teo, Jeffrey Z. Tao, Jinyun Zhang Mitsubishi Electric Research Lab

David Comstock, John Lee, Zheng Shang, Jingning Zhu Huawei Technologies

> Yanling Lu, Ting Li Hisilicon Technologies

Sean Cai, Qu Hongyun ZTE USA

Daqing Gu, Anxin Li DoCoMo

1. INTRODUCTION

The initial network entry process for MS is defined in IEEE Std. 802.16-2004 & 802.16e-2005, Section 6.3.9. In the DL PUSC mode, any segment used in the preamble shall be allocated at least one group (default is 12 subchannels in case of OFDM-2048) in the DL First Zone that contains FCH and DL-MAP. The default

2007-01-18

allocated subchannel sets for segments 0, 1, 2 are subchannels 0-11, 20-31, and 40-51, respectively. For example, when segment 0 is detected in the DL preamble of the frame structure, the immediately followed First Zone PUSC (i.e., FCH and DL-MAP) messages shall use at least 12 subchannels 0-11 to encode the FCH and DL-MAP control signaling. Note that the First Zone PUSC subchannel can cause interference with the same segment value.

In the relay enabled system, a Mobile RS (MRS) can be turned on at anytime and anywhere. If the MRS coverage area overlaps its neighbors RSs/BSs coverage areas and the same segment values are used, then in this situation co-channel interference may arise and MS/SS (mobile station/subscriber station) may not decode Cell IDs and control messages such as FCH and DL-MAP signals. In order to mitigate interference, we propose MRS preamble and segment re-assignment methods used as the MRS moves.

2. MOBILE RS PREAMBLE SEGMENT CONFIGURATION

After the mobile RS has registered with the MR-BS, it may move. In this case, two RSs (nomadic/mobile/fixed RS) or BS may end up geographically close to one another and they may interfere with each other if they have the same segment value. In order to mitigate co-channel interference due to the RS mobility, we propose a preamble segment re-assignment method associated with mobility handover

2.1 Mobile RS Preamble Segment Re-Assignment

During the initial network entry procedure, the MR-BS has assigned a segment "0", "1", or "2" to each RS in its coverage area. MR-BS can simply re-assign a different segment value to mobile RS that is interfering with other fixed/nomadic RSs. If both RSs are mobile RS, than we can re-assign one of them. Before the mobile RS segment reassignment, the BS/RS will command all the MSs within the mobile RS's serving coverage area to switch to the newly assigned preamble segment at pre-determined action time via MOB_BSHO_REQ and MOB_HO_IND handover procedure as shown in Figure 1. With this virtual handover process, all the MSs do not really handover to a different RS. The targeted RS is the same as the previous serving RS but re-assigned a new RS preamble segment value and all the MSs controlled by this RS switch to this newly re-assigned RS preamble segment re-assignment method is shown in Figure 1. Mobile RS may simultaneously transmit both the old and newly assigned preambles, together with the associated control signaling, for some (configurable) period of time in order to support fast ranging.




Figure 1. The message signaling for the mobile RS preamble segment re-assignment.

3. CHANGES TO THE SPECIFICATION

Insert the following text at the end of 6.3.2.3.7

For a MR-BS operation, the REG-REQ shall contain the following TLV.

RS_capability_support TLV (11.7.27)

Insert new subclause at the end of 6.3.9

During the network entry and registration process, the MRS acts as a MS/SS and use REG-REQ message to inform the MR-BS that it has relay capability to MR-BS.

Insert new subclause (6.3.2.3.64)

*** Note: The same messages of RS_CONF-REQ and RS_CONF-RSP have been used in the proposal of FRS preamble segment assignment.

Syntax Size Notes RS CONF-REQ_Message_Format() { Management Message Type = TBD 8 bits N Preamble 2 bits N_Preamble=0 specifies NULL preamble (e.g., Transparent RS) N_Preamble=1 assigns one preamble to the RS N_Preamble=2 assigns two preambles on different segments to the RS N_Preamble=3 assigns three preambles on different segments to the RS 6 bits Reserved For (i=0, i<N_Preamble; i++){ Preamble index 8 bits Assign a preamble index value to the potential RS **TLV Encoded Information** Variable **TLV Specific**

6.3.2.3.64 RS preamble configuration request (RS_CONF-REQ) message

N-Preamble

N_Preamble is the number of preamble index assigned to the potential RS. For example, N-Preamble=0 means the potential RS does not transmit preamble acting as a Transparent RS. If N-Preamble=1 means the potential RS transmit one preamble index (i.e., the RS transmit one segment value and one IDCell) acting as a Non-Transparent RS. If N-Preamble=2 means the potential RS transmit two preamble index (i.e., the RS transmit two different segment values and IDCells) acting as a Non-Transparent RS.

The RS_CONF-RSP shall contain the following TLVs: HMAC/CMAC Tuple (see 11.1.2) The HMAC/CMAC Tuple shall be the last attribute in the message.

Insert new subclause (6.3.2.3.65)

6.3.2.3.65 RS preamble configuration response (RS_CONF-RSP) message

Syntax	Size	Notes	
RS_CONF-RSP_Message_Format() {			
Management Message Type = TBD	8 bits		
Result	1 bit	0 = Fail	
		1 = Success	
Reserved	7 bits		
TLV Encoded Information	Variable	TLV Specific	
}			

Result

Result indicates the RS preamble configuration request message; a bit of 0 indicates the message fail and a bit of 1 indicates the message success.

The RS_CONF-RSP shall contain the following TLVs: HMAC/CMAC Tuple (see 11.1.2) The HMAC/CMAC Tuple shall be the last attribute in the message.

Insert new subclause (6.3.22.4)

6.3.22.4.1 MRS Handover with preamble index changes

When MRS coverage area overlaps with another infrastructure stations coverage area, MR-BS may initiate MRS preamble reassignment procedures as define in section 9.4. If MRS preamble is changed then all the active MS connections are handed over to the same physical MRS after the RS preamble is changed using procedures in 6.3.22. The MRS segment reassignment procedure is executed during or after handover decision and initiation stage. All the MSs within the MRS's serving coverage are switched to the newly assigned preamble segment at pre-determined action time via MOB_BSHO_REQ/RSP.

Insert new subclause (9.4)

9.4 RS configuration

After the measurement report from RS neighborhood discovery process, MR-BS may send a RS preamble configuration request (RS_CONF-REQ) message (6.3.2.3.64) to the RS for configuring the preamble segment and IDCell values. MR-BS may assign NULL preamble to the RS, thereby configuring it as a Transparent RS. Also, an RS may be assigned multiple preambles in order to proceed with the MS virtual handover process as defined in section 6.3.22.4.1. The RS sends a RS_CONF-RSP message to the MR-BS for responding the preamble assignment result.

*** The same TLV of RS_capability_support has been used in the proposal of FRS preamble segment assignment.

Insert new subclause 11.7.27

11.7.27 RS_capability_support

The "RS_capability_support" field indicates the potential RS capability. A bit of 1 indicates "support RS capability".

Туре	Length	Value	Scope
TBD	1	Bit #0=1; Support FRS capability.	REG-REQ
		Bit #1=1; Support MRS capability	
		Bit#2- bit #7; Reserved	