Project IEEE 802.16 Broadband Wireless Access Working Group http://ieee802.or			
Fast Uplink Bandwidth Allocation for Intermittent Short Packets			
Date Submitted	2005-01-20		
Source(s)	Yerang Hur, Bong Ho Kim, Jungnam Yun, Jaehyeong Kim, Seyoung KimVoice: 408-986-1140 Fax: 408-986-1145 		
Re:	Corrigendum to IEEE Std 802.16-2004		
Abstract	Intermittent short packets cause network delays if bandwidths are allocated with contention-based CDMA bandwidth requests mechanism for OFDMA. This contribution proposes a contention-based bandwidth request mechanism for fast uplink bandwidth allocation so that OFDMA system can deliver intermittent short packets fast.		
Purpose	Review and adoption of the proposed text change into Corrigendum to IEEE Std 802.16-2004		
Notice	This document has been prepared to assist IEEE 802.16. It is offered as a basis for discussion and is not binding on the contributing individual(s) or organization(s). The material in this document is subject to change in form and content after further study. The contributor(s) reserve(s) the right to add, amend or withdraw material contained herein.		
Release	The contributor grants a free, irrevocable license to the IEEE to incorporate material contained in this contribution, and any modifications thereof, in the creation of an IEEE Standards publication; to copyright in the IEEE's name any IEEE Standards publication even though it may include portions of this contribution; and at the IEEE's sole discretion to permit others to reproduce in whole or in part the resulting IEEE Standards publication. The contributor also acknowledges and accepts that this contribution may be made public by IEEE 802.16.		
Patent Policy and Procedures	The contributor is familiar with the IEEE 802.16 Patent Policy and Procedures < <u>http://ieee802.org/16/ipr/patents/policy.html</u> >, including the statement "IEEE standards may include the known use of patent(s), including patent applications, provided the IEEE receives assurance from the patent holder or applicant with respect to patents essential for compliance with both mandatory and optional portions of the standard." Early disclosure to the Working Group of patent information that might be relevant to the standard is essential to reduce the possibility for delays in the development process and increase the likelihood that the draft publication will be approved for publication. Please notify the Chair < <u>mailto:chair@wirelessman.org</u> > as early as possible, in written or electronic form, if patented technology (or technology under patent application) might be incorporated into a draft standard being developed within the IEEE 802.16 Working Group. The Chair will disclose this notification via the IEEE 802.16 web site < <u>http://ieee802.org/16/ipr/patents/notices</u> >.		

1 2

3 4


.1

Fast Uplink Bandwidth Allocation for Intermittent Short Packets

Yerang Hur, Bong Ho Kim, Jungnam Yun, Jaehyeong Kim, Seyoung Kim POSDATA Co., Ltd.

5 1. Problem Statements

For delivering the intermittent short packets, an SS needs to request uplink bandwidth using contentionbased OFDMA BW requests described in 6.3.6.5. Figure 1 shows the contention-based OFDMA BW
allocation mechanism described in 6.3.6.5. It requires minimum five message transfers between BS and SS:
three from BS and two from SS until the SS starts to send data. This overhead can be reduced to three
messages: two from BS and one from SS, if the SS informs a BS that data to be transmitted are short.



8

20 21 22

Figure 1: Contention-based OFDMA BW Allocation Mechanism

23 2. Remedy

1. A SS sends a bandwidth request using the Fast BW Request CDMA code, if the amount of the packets is less than *m* bytes, where *m* is implementation specific.

2. If the Fast BW Request code is identified successfully, the BS sends Fast_BW_Allocation_IE to the SS with
 duration allocated.

3. The SS transmits data over the bandwidth allocated.

Figure 2 illustrates how the BS allocates bandwidth for short packets using the proposed method.

- 31
- 32
- 33 34
- 35
- 6
- 37
- 18

005-01-20		IEEE C802.16maint-05/023	
BS	•		•
UL-MAP with UIUC=12	Fast BW request CDMA code	Fast_BW_Allocation_IE	data
		v	
SS Figure 2: Cont	ention-based OFDMA	BW Allocation Mechar	nism with Fast_ BW_Allocation_IE
Figure 2: Cont	ention-based OFDMA	BW Allocation Mechar	nism with Fast_ BW_Allocation_IE

3. Proposed Changes

7 [Add this to line 21, page 27, IEEE 802.16maint-04/10]

9 Add the text to the end of Section 6.3.6.5 Contention-based CDMA Bandwidth Requests for WirelessMAN-10 OFDMA

- Also, the WirelessMAN-OFDMA PHY supports optional contention-based fast bandwidth request mechanism
- 13 for short packets. The SS may request the bandwidth for the short packets using the fast bandwidth request
- mechanism, if the amount of the data is less than *m* bytes where *m* depends on implementation. The SS may
- transmits a Fast BW Request code defined in 8.4.7.3 for requesting bandwidth using Fast BW Request
 mechanism, when Fast BW Request opportunity is given as defined in Table 285, Section 8.4.5.4. If the Fast
- BW Request code is identified successfully by the BS, the BS sends Fast BW Allocation IE defined in Table
- 301, Section 8.4.5.4.15 to the SS with duration allocated. This allows the SS to send short packets over the
- 9 bandwidth allocated by Fast_BW_Allocation_IE.
- **\$0**

.8

-)/ |8
- ,0

1 2 3

[Modify the row 9 of Table 287, page 59, Section 8.4.5.4, IEEE 802.16maint-04/10]

4

Syntax	Size	Notes
Ranging Method	2 bits	0b00 –Initial Ranging over two symbols
		0b01- Initial Ranging over four symbols
		0b10- <u>Fast BW Request</u> /BW Request/Periodic Ranging over one symbol
		0b11 – <u>Fast BW Request</u> /BW Request/Periodic Ranging over three symbols

- 5

7

- 6
- [Insert Section 8.4.5.4.15 Fast Bandwidth Allocation IE into the end of page 67, IEEE 802.16maint-8 04/10] 9
- 0
- 8.4.5.4.15 Fast Bandwidth Allocation IE . 1
- .2
- [Add Table 303 and the text into Section 8.4.5.4.15 Fast Bandwidth Allocation IE as follows:]
- .4

.3

5

Table 303-Fast_BW_Allocation_IE

<u>Syntax</u>	<u>Size</u>	Notes
Fast BW Allocation IE(){		
Extended UIUC	<u>4 bits</u>	<u>Fast bandwidth allocation = $0x06$</u>
<u>Length</u>	<u>4 bits</u>	$\underline{\text{Length} = 0x03}$
Duration	<u>6 bits</u>	
<u>Repetition Coding Indication</u>	<u>2 bits</u>	<u>0b00 – No repetition coding</u>
		<u>0b01 – Repetition coding of 2 used</u>
		<u>0b10 – Repetition coding of 4 used</u>
		<u>0b11 – Repetition coding of 6 used</u>
Fast Bandwidth Request Code	<u>8 bits</u>	
Symbol Index	<u>8 bits</u>	

2005-01-20

	<u>Subchannel Index</u>	<u>7 bits</u>		
	reserved	<u>1 bit</u>		
	}			
1	· ·		·	
2	Duration			
3	Indicates the duration, in units of OFDMA slots, of the allocation less than 63 slots.			
4	Repetition coding indication			
5	Indicates the repetition code used inside the allocated burst.			
6	Fast Bandwidth Request Code			
7	Indicates the CDMA code sent by the SS for Fast Bandwidth Request.			
8	Symbol Index			
9	Indicates the index of starting OFDMA symbol used by the SS.			
.0	Subchannel Index			
.1	Identifies the subchannel used by the SS to send the CDMA code.			
.2				
.3				
.4	[Add the text into the beginning of Section 8.4.7.3 Ranging codes, page 71, IEEE 802.16maint-04/10]			
.5	The number of available codes is 256, numbered 0255. Each BS uses a sub-group of these codes, where the			
.6	sub-group is defined by a number S, $0 \le S \le 255$. The group of codes will be between S and			
.7	((S+N+M+L+P) mod 256).			
.9				
20	- The first N codes produced are for init	ial-ranging. For example, for th	e default case of	
21	two sub-channels in the ranging channel, clock the PRBS 144 x (S mod 256) times to			
22	144 x ((S+N) mod 256) - 1 times.			
23 24	- The next <i>M</i> codes produced are for per case of two subchannels in the ranging of			
24 25	case of two subchannels in the ranging channel, clock the PRBS 144 x (($N + S$) mod 256) times to 144 x (($N + M + S$) mod 256) -1 times.			
26	- The next L codes produced are for bandwidth-requests. For example, for the default			
27	case of two subchannels in the ranging channel, clock the PRBS 144 x (($N + M + S$)			
28	mod 256) times to 144 $x ((N+M+L+S) mod 256) - 1$ times.			
29 20	- The next P codes produced are for fast-bandwidth-requests. For example, for the default case of two subchannels in the ranging channel, clock the PPRS $144 \times ((N+M+I+S))$			
30 31	case of two subchannels in the ranging channel, clock the PRBS $144 x ((N + M + L + S))$ mod 256) times to $144 x ((N + M + L + P + S)) mod 256) - 1$ times.			
52	$\frac{1}{1000} \frac{2}{200} \frac{1}{1000} \frac{1}{100} \frac{1}{1000} $			
13				
\$4				
15				
6				

2

1

[Add the following entry to Table 353, page 79, Section 11.3.1 UCD PHY-specific channel encodings--WirelessMAN-OFDMA, IEEE 802.16maint-04/10]

4 5

3

Name	Type (1 byte)	Length	Value (variable length)
Fast-bandwidth-request codes	<u>174</u>	1	<u>Number of fast</u> <u>bandwidth request codes.</u> Possible values are 0-
			<u>255.</u>

- 6
- 7
- 8

9 [Add this to page 79, Section 11.3.1, IEEE 802.16maint-04/10]

- 0 Modify the following entry of Table 353, Section 11.3.1 UCD PHY-specific channel encodings--
- 1 WirelessMAN-OFDMA
- .2

Name	Type (1 byte)	Length	Value (variable length)
Start of ranging code groups	155	1	Indicates the starting number, S, of the group of codes used for this uplink. All the ranging

.3